

ADDENDUM NO. 2

NEW BUILDING FOR CELINA ELECTRICAL DEPARTMENT

CITY OF CELINA, OHIO

Project No. 220803.02

Index of Contents

Addendum No. 2, 6 Items, 2 Pages

Attachments

None

June 22, 2022

I hereby certify that this Addendum was prepared by me or under my direct supervision and that I am a duly registered Engineer under the Laws of the State of Ohio.

ACCESS ENGINEERING SOLUTIONS



TO: ALL BIDDERS OF RECORD

ADDENDUM NO. 2 to Drawings and Specifications for the New Building for Celina Electrical Department project, City of Celina, Ohio; as prepared by Access Engineering Solutions, Celina, Ohio.

This Addendum shall hereby be and become a part of the Contract Documents the same as if originally bound thereto.

The following clarifications, amendments, additions, revisions, changes, and modifications change the original Contract Documents only in the amount and to the extent hereinafter specified in this Addendum.

NOTE: Bidders are responsible for becoming familiar with every item of this Addendum and acknowledge the receipt of said addendum on the bid forms.

ITEM NO. 1 – Bid Opening Date

- a) The bid opening date has been changed to Tuesday, June 28, 2022 at 11:00 a.m.

ITEM NO. 2 – Specification Section 00100 – Instructions to Bidders

- a) Section 24.01 Engineer's Estimate: The Engineer's estimate for this project has been changed to \$2,250,000.

ITEM NO. 3 - Specification Section 00200 – Information Available to Bidders

- a) Varco Pruden and Reeds Metals are approved pre-engineered metal building manufacturers.

ITEM NO. 4 – Construction Drawings – Sheet P-1

- a) Contractor to supply and install a utility sink on the backside of the wall at the proposed shower location. Utility sink to be Mustee Model 15F with 4" center holes and Delta model 2133LF two handle faucet in chrome finish. Include necessary hot and cold water supply lines and drain piping.

ITEM NO. 5 - Specification Section 16441 – Panelboards

- a) Correction that all panelboards are to be NEMA Type 1 or better, they are not required to be NEMA Type 4X as stated in the specifications.

ITEM NO. 6 – Construction Drawings – Sheet E-3

- a) Clarification that the contractor is to supply and install the 320 A meter base. The City will install a transformer and bring the power to the meter base.