SECTION 00 10 30
BID FORM

Item	Description	Est Qty	Unit	Unit Price	Total Price
1	Mob., Demob., Bonds, and Insurance	1	LS		
2	Chain Link Security Fencing and Gates at Well Sites and Front Entrance	1	LS		
3	Wellfield Entry Gate (20' wide double gate, continuous arch, spear top)	1	EA		
4	Industrial Fencing, 8' Sections, Spear Top, 84" Tall, 6"x6" Posts	300	LF		
5	Crushed Stone Drive with Geogrid and Gravel with Geotextile at Well Sites	1	LS		
6	Security Cameras at Well Sites	3	EA		
7	Bollards Type 2	6	EA		
8	Seeding & Grading	1	LS		
9	Submersible Pump, Motor, & Drop Pipe	3	EA		
10	Pitless Adapter	3	EA		
11	8" Class 52 D.I. Water Main with fittings, glands, gaskets, restraints, and poly encasement	75	LF		
12	10" Class 52 D.I. Water Main with fittings, glands, gaskets, restraints, and poly encasement	600	LF		
13	12" Class 52 D.I. Water Main with fittings, glands, gaskets, restraints, and poly encasement	1,210	LF		
14	10" Gate Valve & Box	3	EA		
15	Precast Valve Meter Vault with Valves, Meters, Piping, Hatch, and Sample Station	3	EA		
16	Well Platform PW-2,Complete with Foundation, Stairs, Handrail, Steel Structure	1	LS		
17	Well Platform PW-1 & PW-3, Complete with Foundation, Stairs, Handrail, Steel Structure	2	LS		
18	Moving Generator for Revis & Installing on Middletown Junction	1	LS		
19	Electrical Compoments (Wire, VFD, MPZ, Disconnect Switch, Distribution Panel, ATS) - PW-2	1	LS		
20	Electrical Compoments (Wire, VFD, MPZ, Disconnect Switch) - PW-1 & PW-3	2	EA		
21	Underground Electrical Conduit and Wire between Wells	1	LS		
22	Conduit and Fiber from Revis to Well Platforms at Middletown Junction	1	LS		
23	Underground Conduit and Electrical wire from Duke Transformer (HDD) to PW-2	1,100	LF		
24	Instruments and Control Panels (Programming provided by others)	1	LS		
25	H-3 Fire Hydrant Assembly	3	EA		
26	Clearing and Grubbing	1	LS		
27	Final Cleanup and Restoration	1	LS		
28	Allowance for Clearing of Invasive Underbrush at Site	1	LS	$ 15,000	$ 15,000
29	Duke Energy Wire/Transformer Fee	1	LS	$ 60,000	$ 60,000
	TOTAL BID				